



PROJECT INTEGRATION

Working group update
CSLF Edmonton - 19 May 2011

CONTENTS


- Background and Objective
- Scope and WG Members Feedback
- Progress made
- Summary and Next Actions

BACKGROUND - THEMATIC GROUPS

- Discussions held in margins of GHGT-10 with Members -~70 attendees
- Presentations on 4 themes identified from projects
 - Hub Development Challenges
 - Managing Impacts of CO₂ storage on groundwater
 - Storage learning from EOR operations
 - Project Integration Challenges
- Themes accepted as being appropriate and useful
- Implementation of the Thematic Groups is one of the key actions for the Global CCS Institute in 2011/2012

OBJECTIVE - PROJECT INTEGRATION WG

- Address the need for whole of CCS project integration of risk management and dependencies
- To inform the proponents and prospective funders of early stage project proposals, to enable them to incorporate key learnings from prior projects into their plans and schedules



SCOPE – PROJECT INTEGRATION WG (CIRCULATED TO WG MEMBERS Q1 2011)

Subsequent Steps

- Collect high level project development schedules (incl. resources) presented primarily as Gantt charts
- Describe scope of stages, key tasks and decisions points in CCS projects
- Identification of project inter-dependencies critical paths and timing determinants
- 4. Comparison of project staging and commentary on key challenges and risk management
- 5. Key learnings regarding project integration and their application to new projects, including preparation of guidance schedules, tasks and resourcing descriptions


SCOPE - PROJECT INTEGRATION WG

WG Members Feedback


- Include information from projects that have failed and key decisions <u>not</u> made in their project development cycle
- Careful handling of proprietary data from projects
- Accommodate for context specific issues when developing "generic" project development guidelines
- The development of project development software might be too ambitious for this WG – and it was noted that most projects will use their own software (to which the WG can provide valuable input)
- Make sure the work is not duplicating the activities undertaken by the EU CCS Project Demonstration Network (or any other project network for that matter)

PROGRESS MADE – PROJECT INTEGRATION WG GANTT CHARTS COLLECTED FROM PROJECTS

Indicative project timeline – Power plant with CO₂ capture and storage



PROGRESS MADE – PROJECT INTEGRATION BASED ON GANTT CHARTS "GENERIC" TASKS HAVE BEEN IDENTIFIED FOR EACH STAGE OF THE PROJECT LIFECYCLE



PROGRESS MADE – PROJECT INTEGRATION WG KEY PROJECT TASKS ARE DOCUMENTED ON "OPENCCS" ACCORDING TO THE PROJECT LIFECYCLE

- OpenCCS is a collaborative area for building and sharing methodologies, best practices and lessons learned regarding CCS Project Development
- OpenCCS is structured as a "project development guide" and consists of three layers (see following slides)
- Initially it is not an open editing model:
 - Parsons Brinckerhoff has been contracted to support the development of content for OpenCCS
 - As the content develops, controls are in place to lock down aspects of content of OpenCCS and provide it with maturity ratings
 - Experts are sought to review content that is currently hosted behind a firewall

OPENCCS STRUCTURE - 3 FRAMES TO SHOW GRANULARITY IN PROJECT DEVELOPMENT

- <u>Level 1 frame</u> provides the main structure for OpenCCS; i.e. the generic project development guide.
- Level 2 frame describes around 20 activities necessary in a certain of development phase of the project, e.g.:

Activity	Description (Define Phase – Capture Plan)
Site Selection	Undertake selected site survey Undertake topographical survey Soil investigation Identify sensitive receptors (noise / visual impacts) Negotiate and finalise site leasehold, ready for execution
Capital / Operating Costs	Estimate order of magnitude costs of the capture plant (both capital (+/-10-15% accuracy) and operating (+/-5-10% accuracy)

Level 3 frame lists the key tasks and outcomes in detail and references are made to existing work in this area and attention is paid to possible bottlenecks in relation to this particular aspect of the project.

GLOBAL CCS INSTITUTE

OpenCCS structure – Level 1 data: An Example

Areas	1. Identify Stage	2. Evaluate Stage	3. Define Stage	4. Execute Stage	5. Operate Stage	6. Closure Stage	
General Approach	Consider high-level options Short list options for further study "What could it be?"	·		Undertake remaining (detailed) design Build organisation to commission and manage asset Undertake construction activities Undertake commissioning	Operate the asset within regulatory compliance requirements, for the operating life of the asset	Decommission asset to regulatory compliance requirements Rehabilitate site for future defined use Build organisation and provide resources for post-closure	
Specifics for Capture	Concept Studies Identify potential of the new or expanded business Consider new-build or retrofit for capture Consider saline reservoir or EOR or other for storage/beneficial reuse Document general features of the project Estimate order of magnitude costs of the project (both capital (+/-30-35% accuracy) and operating (+/- 15-20% accuracy))	Prefeasibility Studies Consider different capture technologies Consider different EPC contractors Consider different process, location and project configuration options Consider different capacities for the project Assess the likely technical and economic viability of the project Recommend the preferred option and size for final study Estimate costs of the project (both capital (+/- 20-25% accuracy) and operating (+/- 10-15% accuracy))	Feasibility Studies Undertake front end engineering design (FEED) studies, clearly recommending one processing, location and project configuration, and prevent the need to be materially varied after project commitment Estimate costs of the project (both capital (+/- 10-15% accuracy) and operating (+/- 5-10%; closer to 5% accuracy)) Select construction contractor and delivery approach (i.e. EPC) Obtain all required regulatory approvals Provide the basis for making an investment decision, and make final investment decision for construction of capture facility	Project Execution Complete the design detail for building the carbon capture asset Build the organisation and systems to manage the carbon capture asset Build the carbon capture asset • On time • On budget • To scope and quality Commission the carbon capture asset to operating state	Asset Operation Ramp-up operation of the carbon capture asset to ascertain true performance Modify the carbon capture asset (as necessary) to achieve required performance Operate the carbon capture asset to achieve required performance over asset life Maintain the carbon capture asset to achieve required asset life Modify the carbon capture asset to comply with legislated regulatory changes Modify the carbon capture asset to realise identified opportunities	Asset Decommissioning Operation of asset (i.e. power plant with capture) ceased Modify the asset (as necessary) to achieve required decommissioned state • On time • On budget • To scope and quality Asset sites decommissioned and rehabilitated to required condition Establish organisation for post-closure stage (as necessary)	
Specifics for Transport	Concept Studies Consider pipeline or other CO2 transport options Consider existing or new transport route Consider single or multi- user transport route Estimate order of magnitude costs of the project (both capital (+/- 30-35% accuracy) and operating (+/- 15-20% accuracy))	Prefeasibility Studies Consider different transport routes Recommend the preferred transport route and capacity for final study Estimate costs of the project (both capital (+/- 20-25% accuracy)) and operating (+/- 10-15% accuracy))	Feasibility Studies Undertake front end engineering design (FEED) studies, clearly recommending one transport route Estimate costs (both capital (+/- 10-15% accuracy) and operating (+/- 5-10%; closer to 5% accuracy)) Select construction contractor and delivery approach (i.e. EPC) Obtain all required regulatory approvals Make final investment decision for construction of transport facilities	Project Execution Complete the design detail for building the transport asset Build the organisation and systems to manage the transport asset Build the transport asset • On time • On budget • To scope and quality Commission the transport asset to operating state	Asset Operation Operate the transport asset to achieve required performance over asset life Maintain the transport asset to achieve required asset life Modify the transport asset to comply with legislated regulatory changes Modify the transport asset to realise identified opportunities	Asset Decommissioning Operation of asset (i.e. pipeline) ceased Modify the asset (as necessary) to achieve required decommissioned state • On time • On budget • To scope and quality Asset sites decommissioned and rehabilitated to required condition Establish organisation for post-closure stage (as necessary)	
Specifics for Storage	Site Screening Studies Define screening basis Develop screening plan Review available data and identify potential sites Estimate capacity and level of uncertainty Shortlist storage sites	Site Assessment Studies Obtain exploration permit Define selection basis and develop selection plan Acquire data, test, analyse, rank risks Select site and engineering concept	Site Selection Studies Specify performance targets Prepare CO2 storage development plan Evaluate compliance with regulations and qualification goal Obtain storage permit	Design and (Initial) Construct Select construction contractor and delivery approach for (initial) storage assets (i.e. EPC) Complete the design detail for building the (initial) storage assets (i.e. wells, feeder piping) Build the organisation and systems to manage the storage assets Build the (initial) storage assets On time On budget To scope and quality Commission the (initial) storage assets to operating state	Operate (Remaining Construct) Operate the storage assets to achieve required performance over asset life Develop plan for permit review/re- qualification Reassess risks Adjust performance targets Adjust CO2 storage development plan Storage permit renewal Complete the design detail for building the (remaining) storage assets (i.e. wells, feeder piping) Select construction contractor and delivery approach for (remaining) storage assets (i.e. EPC)	Close Assess if conditions for site closure have been met Define closure basis Develop closure plan Update storage performance forecast and environmental impact assessment Obtain certificate of fitness for closure Initiate decommissioning Transfer of responsibility for site	


OPENCCS STRUCTURE

▶ Sean McClowry

OpenCCS Search OpenCCS OpenCCS is an open, collaborative wiki that everyone helps to write. OpenCCS is for sharing methodologies, best practices and lessons learned in relation to the implementation of Carbon Capture and Storage. Search Find out how you can contribute. Toolbox Revisions Convert Edit Delete Outline Activities for CO2 Capture during the Define Phase Page status: Draft This page is an open access page, and open for editing. Protect Page status: Draft Create a new page Page Edit this page Watch this page -Editing-View All OpenCCS pages Protected: What links to this page Developing Reviewing Mature Protect this page from further edits Recent changes You can edit this page Shown below are the activities required during: < No highlighting > . CO2 Capture Edit Page Please edit this page to improve it · The Define phase of the CCS program Protect this page . Each Activity links to a more detailed description of the approach This page is not protected. Anyone with permission to see this page can edit it. For further information on this framework, see: Protect this page · An overview of the openCCS Content Model Reviewer · A high level overview of all stages across capture, transport and storage This article was last reviewed by Sean McClowry on 27 Apr 2011 and marked as Draft You are currently a reviewer of this document Activity Description **Current reviewers Project Context and** Finalise the Business Case for Power Plant and Capture Plant. Opportunity Definition The following Users are reviewers of this article: and Recommendation Prepare Board Paper identifying: ▶ Angus Henderson Project Status ▶ Klaas van Alphen Martin Oettinger Business Drivers

Market tested project costs

INFORMATION SOURCES - PROJECT INTEGRATION



KNOWLEDGE TOPICS COVERED

	Feasibility/FEED			Case Studies			
Project	Capture	Transport/ Infrastructure	Storage and MMV	Finance and Commercial	Policy, Legal and Regulation	Public Engagement	Risk and Environment
Rotterdam CCS Network Project		✓			✓		✓
Romanian CCS Demo Plant	✓	✓	✓	✓	✓		
Trailblazer Energy Center	✓		✓	✓	✓	✓	
Nelson 6 CCS Project (Phase 1)	✓				✓	✓	
TransAlta Pioneer	√	✓	✓	✓	✓	✓	✓
AEP Mountaineer	✓		✓				
Chiyoda Project		✓					
ROAD Project	✓			✓	✓	✓	✓

INFORMATION SOURCES – PROJECT INTEGRATION EXAMPLES OF REPORTS FROM PROJECTS

Knowledge products – Trailblazer Tenaska

Development History of the Project

CO₂ Technology Evaluation, Methodology and Criteria

Public Engagement activities

Report on Steam Turbine Sizing

Carbon Capture Plant Layout Integration with a New Coal Fired Power Generating Facility

Deep Saline Sequestration Study





Knowledge products – Rotterdam CCS Network Project

Detailed technical and cost reports for 3-4 storage sites in Dutch sector North Sea

Historic Case Study on the Rotterdam CCS network

Methodology report on the Independent Storage Assessment

INFORMATION SOURCES – PROJECT INTEGRATION EXAMPLES OF UPCOMING REPORTS FROM N-A

Knowledge products – Project Pioneer (Transalta)

Report on the Regulatory gaps for implementing CCS

Case Study on the socio - economic impact of an integrated CCS Project

Special report on the Construction execution strategy for the Project

New developments in MMV technology

Non confidential version of FEED study report of the integrated project

Knowledge products – Mountaineer Project (A.E.P)

CO₂ Compression report

Report on CCS integration issues

The business case – financial modelling and local impacts of CCS

Non confidential version of FEED study report of the integrated project

Knowledge products – Tenaska Trailblazer


Building a Consortium to Develop a New Pulverised Coal Plant with Post-combustion Capture

Bridging the commercial gap for CCS (ERCOT base load power and EOR market factors)

Financing a new pulverized coal plant with CCS.

Non confidential version of FEED study report

INFORMATION SOURCES-PROJECT INTEGRATION PROJECT SURVEY WORK



LSIPs: Global Industry sector

Power generation
Gas processing
Multiple capture facilities
Other industry

Storage type

- EOR (Enhanced oil recovery)
- Δ Deep saline formations
- Depleted oil and gas reservoirs
- Deep basalt formations
- Various/not specified

SUMMARY & NEXT STEPS – PROJECT INTEGRATION

Progress has been made with regard to data gathering, but WG Member involvement is required in the next steps Next Steps

- 1. Review and improve project related content on OpenCCS
- Identification of project inter-dependencies critical paths and timing determinants
- 3. Comparison of project staging and commentary on key challenges and risk management
- 4. Summary of key learnings and application to new projects
- 5. The first work program could result in a "special report":
 - a) Key technical integration issues; or
 - b) <u>Key interdependencies in project schedules and risk</u> <u>mitigation strategies</u>

SUMMARY & NEXT STEPS - PROJECT INTEGRATION

Next Steps – Timing

- A password and user manual for OpenCCS will be send to the WG Members – Q2 2011
- 2. A chair will be appointed to convene a face to face Working Group Meeting (Dr Klaas van Alphen will perform a secretariat role) Q2 2011
- 3. A Working Group Meeting with Technical Group Members and Interested Project Proponents will be organized to discuss results and refine the work scope with regard to the preparation of specific reports Q3-Q4 of 2011
- 4. Technical Group Members will be kept informed regarding the agenda setting process for the meeting Q3 -2011