

Lacq CCS Integrated Pilot

A First

J.Monne – MGR Project Manager
TOTAL EP – R&D Division





Contents

- Lacq pilot project overview
- Lacq pilot project technical description
- Surface Operational Feedback
- Sub-surface Operational Feedback
- Environmental Monitoring plan and Feedback
- Economic
- Conclusion



Lacq pilot project overview



TOTAL



CCS pilot, Lacq, France

Objectives

- To Demonstrate the technical feasibility and reliability of an integrated onshore Carbon Capture and Storage scheme for steam production at a reduced scale (1/10th of future facilities).
- To acquire operational experience and data to up-scale with cost reduction the oxy-combustion technology from pilot (30MWth) to industrial scale (200MWth).
- To develop geological storage qualification methodologies
- To develop monitoring methodologies on site to prepare future larger scale long term onshore storage projects. (Micro seismic monitoring, Environmental monitoring..)



Lacq Field Test Compressor



Flue gases treatment package

Acquire expertise and reduce costs for future industrial deployment




TOTAL



CCS pilot, Lacq, France

Project description

- Budget : CAPEX 60 M Euros
- Up to 90000 tonnes of CO₂ injected
- Main technical's features
 - Revamping of one existing air combustion boiler to an oxy-combustion boiler (Air Liquid / Alstom)
 - Installation of 2 new CO₂ compressors (Lacq and Rousse)
 - Installation of one Air Separation Unit (Air Liquid)
 - Installation of one flue gas treatment unit / driers
 - Modification of an existing production well to an injection well.




This industrial operation is planned to capture and trap ~ 90,000 tonnes of CO₂ over a 3 1/2-year period (eq to the exhaust emissions of 30,000 cars)





CCS pilot, Lacq, France

Project phasing



Start-up of operational phase: July 3rd, 2009
First CO₂ injection in Rousee reservoir: January 8th, 2010
End of injection: 8th July 2013





CCS pilot, Lacq, France

Permitting and public acceptance

- Permit obtained in may 2009 for capture, transportation and storage based on
 - A « Regulatory » pilot, 1st in Europe
 - Specific risk and impact analysis
 - Permit extension obtained in November 2011
 - Injection until July 2013
- Public dialogue – transparency policy
 - Identification of Stakeholders (ONG, mayors...)
 - Early public meetings in 2007 (4 public meetings)
 - Follow up information committee (7 meetings)
 - Information letter every quarter (14)
 - Hot line
- Scientific Advisory Committee since 2007
- Scientific collaboration program with National Institutes and Universities on Rousse storage
- Project endorsed by the Carbon Sequestration Leadership Forum (CSLF)

Project information also available on www.total.com/corporate-social-responsibility



Lacq pilot project technical description




TOTAL



CCS pilot, Lacq, France

A complete industrial chain



Industrial scale:
30MW_{th} oxycombustion
60 000 t/year CO₂
Integrated within existing facilities



CCS pilot, Lacq, France

Capture description

Air separation unit



Cryogenic unit
(Air Liquide)
O₂ : 240 t/d



Oxy-combustion Boiler



Existing 1957 boiler revamped
by Alstom to oxy-combustion boiler.
Oxyburners developed by Air Liquide
(30 MWth, 40 t/h steam @ 60b, 450 C)



Flue gas cooling tower



Cooling of flue gases
From to 200 C to 30 C



Wet CO₂ compressor



From 1 barg to 27 barg



Dehydration Unit



Outlet : < 20 ppm of water



Transport

CO₂ composition
(@98% O₂ purity)
CO₂ : 92.0 %
O₂ : 4.0%
Ar : 3.7%
N₂ : 0.3%



TOTAL



CCS pilot, Lacq, France

Transport / Compression / Injection Rousse site

City of PAU


Transport

29km long pipe (12" and 8" diameter)


CO₂ in gas phase



Rouse storage



Depleted gas reservoir
@ 450m/GL



Rouse compressor



Pinlet: 27bar Poutlet: 51bar



TOTAL

Surface Operational Feedback



TOTAL



CCS pilot, Lacq, France

Lacq Industrial chain

▶ Air Liquide ASU

😊 No operating issue

▶ Air boiler retrofitted to Oxy-combustion

😊 Start-up on air up to 30% load: no issue – on design

😊 Transition from air to oxy-mode: no issue – on design

😊 Steady state and transients in oxy-mode: no issue – on design

😊 Recently added: an automatic transition from oxy to air-mode – no issue

😊 Overall, smooth operation of oxy-burners / Oxy-boiler

☹️ NOx produced is in the 400 ppm range (@3%O₂ dry)

☹️ Even when operating at 99.5% vol O₂ purity (no N₂ from ASU)

☹️ Source of N₂ is from the commercial gas (~0.4% vol N₂)

▶ Cools down the flue gas from 220 C to 30 C (design was 50 C)

😊 No issue



CCS pilot, Lacq, France

Lacq compressor 1/4

► Wet CO₂ stream compressor

• LMF 3 stage reciprocating non lubricated / Max discharge P=27bar

• Cylinders in cast iron / all other parts made of acid resistant materials

☹ Corrosion problems (now resolved)







CCS pilot, Lacq, France

Lacq compressor: Corrosion remediation 4/4

- ▶ Lower cooling at the cooling tower : set point initially at 50 C lowered to 30 C
 - To condense more water & decrease the dew point of the CO₂ stream before compression
- ▶ Slight increase of compressor suction temperatures
 - To minimize condensation in the compressor
- ▶ Recycling of dry CO₂ (downstream dryers) to compressor inlet
 - To dry the CO₂ stream feeding the compressor and decrease the dew point
- ▶ Gas / liquid separators internals have been improved
 - To minimize liquid carry-over to suction chambers



- ▶ These technical solutions have proven to be effective: no more corrosion has been observed on the compressor since restart



CCS pilot, Lacq, France

Lacq Industrial chain

- ▶ “Air Liquide’ Molecular sieve technology : Measured [H₂O] < 10 ppm vol. compare to a design value of 30 ppm (= water dew point around -50 C)

😊 No issue

- ▶ CO₂ is transported in gas phase at 27bar max

- ÿ 29 km long existing carbon steel pipe (Ø 8" / 12")

- ÿ Dry CO₂ rich stream avoids corrosion

- 😊 No issue

- ▶ Rouse Dry Compressor

- 😊 No issue – Works on design

- ▶ Well head and well

- ▶ Standard gas production technology and materials

- ▶ A work-over of the well was achieved in winter 2010/2011 to install new sensors down hole (micro-seismic arrays)

- ▶ Tubing was inspected: no corrosion

- 😊 No issue

Sub- Surface Operational Feedback





TOTAL



Sub-surface Feedback monitoring

Bottom hole P measurement

- Static reservoir pressure is increasing due to CO₂ injection. The reservoir pressure increase is as per the predictive model. (Eclipse 300 compositional modeling)




Long term pressure impact (bar) of CO₂ injection

- No injection
- 100 kT CO₂ injection

Sub-surface Feedback monitoring

Microseismic monitoring



- ▶ Objective: To monitor caprock integrity
- ▶ Seven subsurface arrays with 4 triaxial sensors in 7 shallow wells (TD: 200m/GL):
 - 6 wells on a 2km radius circle around the injection well;
 - 1 well on the injection site.
- ▶ One sismometer for natural seismicity
- ▶ Online and continuous information
- ▶ Minimum detection: magnitude -2.5
Localization: +/- 250m
- ▶ 9 month baseline survey before injection
- ▶ In addition, one deep array (3 triaxial sensors) in injection well for R&D objectives







Sub-surface Feedback monitoring

Microseismic monitoring

- Calibration by real shots
- Mainly natural seismic activity linked to northern front accident of Pyrenées mountain range (between Iberic and Eurasian plates)
- Good sensitivity of data acquired for R&D with deep arrays, data analysis on-going: many micro-seismic events located around RSE-1, since March 2011 (yellow dots) Magnitude : - 2.5
- Very few micro-seismic events recorded by surface installation

➔ No incidence on Caprock integrity

Magnitude	faille (en m)	Déplacement (en mm)
-3	0.31	0.015
-2	1	0.05
-1	3.1	0.15
0	10	0.50
1	31.6	1.58
2	100	5.00
3	316.2	15.81
4	1000	50.0



Environmental Plan Monitoring and feedback



TOTAL



Environmental monitoring

Soil gas, Water, Fauna & flora

			Winter	Spring	Summer	Autumn	
Environment	Water quality	Surface water (rivers)	Chemistry				
			Bio-indicators				
		Phreatic aquifer (springs)	Chemistry				
			Gronwater	Chemistry			
	Ecosystems	Fauna					
		Flora					
	Soil gas						
Site	Res. & Caprock	Microseismic + P&T	Permanent				
	Injection well	CO2 sensors at injection pad	Permanent				
		Well annulii	Permanent				
		P & T	Permanent				
		Flowrate, Composition	Permanent				
Additional R&D (French National Research Agency, Paris & Nancy Univ., INERIS, IFPEN, BRGM, IPGP etc.)	Soil gas	C isotopy, Inert gas, radon					
	Phreatic aquifer	6 m deep shallow well	Chemistry	Permanent			
		80 m deep shallow well	Chemistry, water level	Permanent			
		Springs	Chemistry,	Permanent			
	Atmospheric CO2 concentration	Flux tower		Permanent			
Infra red and lidar			In test				


Environmental monitoring

Soil gas, Water, Fauna & flora

To detect changes that could be linked to the effect of a CO₂ leakage

Baseline surveys in 2009.

- **Soil gas (35):** CO₂ and CH₄ concentration and flux. C isotopy. Inert gas. Autumn and winter. ●
- **Perched aquifer (4 springs) :** Chemical and mineral content, every 6 months. ■
Indicators: pH, conductivity, carbonates, bicarbonates.
- **Shallow and deep saline aquifers** sampled at selected existing water wells (drinking water supply of Pau). Monitoring idem perched aquifer.
- **Surface water (5 small rivers):** Standardized bio-indicators (diatoms and benthic macro invertebrates) and chemical and mineral content. Every 6 months. ■
- **Fauna and Flora:** Annual inventory of:
 - Flora of representative ecosystems (33 sites)
 - Several amphibians and insects species (50 sites).






Environmental monitoring

Soil gas, Water, Fauna & flora

No deviation from Baseline surveys in 2009 have been recorded..







Conclusion/ Way forward

- At this stage of the pilot (43000 t injected), **the demonstration of the technical feasibility and reliability** of an integrated onshore Carbon Capture and Storage scheme for steam production **has been proved.** (Obj.1)
- **For CO₂ contained in combustion flue gases** (GT, Furnaces, Boilers), current cost evaluations for capture units of industrial size are still high, even for oxycombustion. **More R&D and demonstration projects are needed** before up-scaling and streamlining Capture installations.
- **The design of 200 MWth oxyboiler should be finalized in 2013., thank to the Lacq pilot plant. (Obj.2)**
- **The Lacq pilot** is part of the larger Total CCS technological roadmap . CCS is considered as a valuable contribution to GHG reduction. The Lacq pilot demonstration project is an example of what **kind of project contributes** to the **deployment of this technology by 2030**
- **The main TOTAL's CCS R&D surface activities are to** participate in the **development of breakthrough CO₂ capture technologies** which are required to cut down costs (CLC, Membranes, Cryogenics techno..)
- **The long term CO₂ storage monitoring program** economically and technically viable is still to be developed.(Obj.3)
- **'Transparency'** in communication **with the stakeholders** is one of **the key factor** to reach the **public acceptance**. It remains a permanent "concern" to be taken into account during the whole life of a CCS experimentation and for the future industrial deployment of CCS..

“Innovation is one of the main drivers of sustainable growth in our production”



THANK YOU FOR LISTENING!



DISCLAIMER and COPYRIGHT RESERVATION

The TOTAL GROUP is defined as TOTAL S.A. and its affiliates and shall include the party making the presentation.

Disclaimer

This presentation may include forward-looking statements within the meaning of the Private Securities Litigation Reform Act of 1995 with respect to the financial condition, results of operations, business, strategy and plans of TOTAL GROUP that are subject to risk factors and uncertainties caused by changes in, without limitation, technological development and innovation, supply sources, legal framework, market conditions, political or economic events.

The TOTAL GROUP does not assume any obligation to update publicly any forward-looking statement, whether as a result of new information, future events or otherwise. Further information on factors which could affect the company's financial results is provided in documents filed by TOTAL GROUP with the French *Autorité des Marchés Financiers* and the US Securities and Exchange Commission.

Accordingly, no reliance may be placed on the accuracy or correctness of any such statements.

Copyright

All rights are reserved and all material in this presentation may not be reproduced without the express written permission of the TOTAL GROUP.