

# CO<sub>2</sub>CRC Otway Stage 2: CO<sub>2</sub> Storage in Saline Formation

Dr Maxwell Watson

Program Manager - Storage




CSLF Projects Interaction and Review Team  
01 November 2015, Riyadh, Saudi Arabia

# Presentation Outline

- CO2CRC and its Otway Research Facility
- Past Major Project – Otway Stage 1
- Basis of Otway Stage 2
- Completed Appraisal Activity
- Injection and Monitoring Activity
- Anticipated Outcomes
- Future of the Otway Research Facility

# CO2CRC – Who we are and what we do

CO2CRC undertakes research that is focused on de-carbonising our environment on an industrial scale. We originate and co-ordinate research programs with researcher partners locally and globally, developing technologies to reduce risk and/or cost in CCS, and validate at scale.



# The CO2CRC Otway CCS Research Facility


- Australia's only CO<sub>2</sub> sequestration facility
- Conceptualised in 2003, characterisation since 2004, operating since 2008
- Varying storage options within simple geological structure
- Multiple CO<sub>2</sub> sources and transport options
- Comprehensive & expanding datasets and infrastructure
- Supportive local community
- Politically stable and supportive government







# Overarching Otway Research Facility Principles



- Ensure human health and safety is protected at all times
- Safeguard ecosystems throughout facility lifetime
- Ensure no impact to underground sources of drinking water and other resources
- Engage openly with community
- Comply with regulations
- Meet scientific objectives



# Location of CO2CRC Otway Facility



# Regional Setting





# Core Enabling Legislation – CO2CRC Otway Project

## **Environmental Portfolio Approvals**

- *Environment Protection Act 1970 - Research Demonstration & Development*

## **Impact Assessment and Planning Approvals**

- *Environment Protection and Biodiversity Act 1999 - not a controlled action*
- *Environmental Effects Act 1978 - no environment effects statement*
- *Planning and Environment Act 1987 - planning scheme amended*

## **Petroleum Portfolio Approvals**

- *Petroleum Act 1998 - various petroleum related activities approved*

## **Water Portfolio Approvals**

- *Water Act 1989 - various drilling and injection activities approved*

## **Land Access**

- *Planning and Environment Act 1987*
- *Land Acquisition and Compensation Act 1986*


## **& Common Law**





# Permitted area as per GGS Exemption Regulations 2009



# Natural CO<sub>2</sub> Accumulations



# Characterising CO<sub>2</sub> Storage Processes and the Monitoring Capabilities to Validate Safe Storage



# Presentation Outline

- CO2CRC and its Otway Research Facility
- **Past Major Project – Otway Stage 1**
- Basis of Otway Stage 2
- Completed Appraisal Activity
- Injection and Monitoring Activity
- Anticipated Outcomes
- Future of the Otway Research Facility





# Otway Stage 1 – Complete

## Science Outcomes

Demonstrated safe transport, injection and storage of >65,000 tonnes of CO<sub>2</sub>-rich gas into a depleted gas reservoir.

Monitoring techniques:

- DH pressure, seismic, gas and formation water sampling (inc. tracers)
- Surface: Groundwater, soil, atmospheric, active seismic, micro-seismic



## Additional Outcomes

- Positive regulatory environment
- Successful outreach program to stakeholders and local community

# Highlights

## Exceptional Datasets

- Atmospheric (continuous monitoring)
- Soil Gas
- Seismic
- Reservoir fluids



## Field Validation

- Validation of models in actual field tests
- Fully permitted and operational site
- Availability of CO<sub>2</sub>
- Globally unique advantage



## First of its kind experiments

- First CO<sub>2</sub> storage demonstration project in Australia
- Reducing risk and uncertainty
- Advising regulators and project proponents in Australia and world wide
- A go-to project




# Presentation Outline

- CO2CRC and its Otway Research Facility
- Past Major Project – Otway Stage 1
- **Basis of Otway Stage 2**
- Completed Appraisal Activity
- Injection and Monitoring Activity
- Anticipated Outcomes
- Future of the Otway Research Facility



# Australia's CCS Demonstrated Capabilities



**Depleted Field Storage –**

Otway Stage 1 ✓

**Saline Formation Storage –**


Major storage option

- i.e. Gorgon, South West Hub, CarbonNet, Surat Basin

Not demonstrated in Australia


**Large scale storage options in Australia**

- Depleted oil and gas fields (10s of yrs)
- Saline formations (100s yrs)





# Understanding a CO<sub>2</sub> plume




- Improving Seismic Detection Limits
- Demonstrating Plume Stabilisation
- Increasing Technology Thresholds
- Reducing Surface Footprint
- Reducing Cost

# The CO2CRC Otway Project Stage 2


Stage 2: 2007 – 2020

*Demonstrate that CO<sub>2</sub> storage can be safely conducted at scale within a Saline Formation*

- Appraisal
  - ✓ 2A :Drill CRC-2
  - ✓ 2B: Measure parameters affecting residual and dissolution trapping in a saline formation
  - ✓ 2B Extension: interactions with impurities & well test refinement
- Operation
  - 2C: Spatially track injected CO<sub>2</sub> in a saline formation
    - Minimum detection limit
    - Migration behaviour
    - Stabilisation



# Stage 2 Timeline



# Presentation Outline

- CO2CRC and its Otway Research Facility
- Past Major Project – Otway Stage 1
- Basis of Otway Stage 2
- **Completed Appraisal Activity**
- Injection and Monitoring Activity
- Anticipated Outcomes
- Future of the Otway Research Facility



# Stage 2 Appraisal



## Development of an injection plan that ensures:

- CO<sub>2</sub> containment within storage complex
  - Within tenement
  - Below primary seal
- Suitable plume distribution for meeting science objectives
  - Detectable plume
  - Moderate migration
  - Short time to stabilisation

## Development of a monitoring plan that ensures:

- Monitoring coverage across entire plume
- Monitoring resolution at highest level
  - High Signal to Noise
  - High repeatability
- Overarching Otway Research Facility Principles are maintained

# Stage 2A – Drill CRC-2



# Stage 2B: Residual Gas Trapping Characterisation (2009 – 2011)

Volumetric equation for capacity calculation

$$G_{CO_2} = V_{pore} \times A \times h_g \times \phi \times \rho \times E$$

$A$  = Ar

$h_g$  = Gr

$\phi$  = Av

$\rho$  = De

$E$  = Storage “efficiency factor” (fraction of total pore volume filled by CO<sub>2</sub>)

**Objective: Test capabilities to determine residual gas saturation?**



# Residual trapping measurements trialled

- Five (5) independent measurement approaches to determining residual trapping:
- The methods deployed have different depths of investigations, supply different information, and have difference benefits and limitations

Pressure response (<20 m)

Pulsed neutron logging tool (RST) (<1m)


Thermal testing (Fibre Optics) (1 - 2 m)

Noble gas tracer testing (KR-Xe) (4 - 10 m)

Liquid tracer (reactive ester tracer partitioning) (4 - 10 m)


Dissolution testing (<1 m)

Laboratory core testing





# Stage 2 surface facilities




# Stage 2B Extension (2014 – 2015)

Part 1: Investigate the impacts of gas impurities on the formation water

Part 2: Further characterize residual saturations, evaluate techniques

Otway - Stage 2B Extension


Version: 4, Date: 13 March 2014



- Part 1 funded by COSPL (Callide Oxyfuel Services Pty Ltd) and utilised CO<sub>2</sub> captured at the Callide Oxyfuel project
- Research is a collaborative effort between CO<sub>2</sub>CRC and its research partners, University of Edinburgh (funded by UKCCSRC) and Lawrence Berkley National Laboratories.



# Stage 2C - Far Field Appraisal



# Plume Modelling

Questions addressed:

How does plume distribution influence:

- Seismic response?
- Containment risk?
- Tenement boundaries?

When does plume stabilise?

Dynamic parameters analysed

Geological realisations

Dolomite cement distribution

Model gridding

Relative permeability

Capillary pressures

Injection horizons


Injection rates

Pressure changes


Thermal changes



# Likely plume distribution range




# Containment Risk Analysis



# Fault Risk Assessment: Question 1

What fluid pressure can the fault support before shear reactivation potentially occurs?



*Paaratte Fm at injection horizon,*


For worse case fault scenario >1MPa needed for potential fault reactivation

According to reservoir models, pressure build up at splay fault is ~ 0.05 MPa

∴ Risk of fault reactivation is very low

# Fault Risk Assessment : Question 2

Will the faults act as a barrier for CO<sub>2</sub> flow, or will CO<sub>2</sub> migrate readily across the fault?



Fault Shale Gouge Ratio (SGR) is >25%  
∴ faults are sealing


In specific scenario modelling, 'no fault seal', CO<sub>2</sub> migrates into abutting fault block and contained within the Paaratte, and within tenement.

∴ Risk of across fault leakage is very low



# Fault Risk Assessment : Question 3

Will CO<sub>2</sub> migrate along faults and if so, how far?



Splay fault does not extend through Paaratte vertically

In specific scenario modelling, '*permeable fault*', CO<sub>2</sub> migrates partly up splay fault only, and is contained within the Paaratte and within tenement

∴ Risk of along fault leakage is very low

# What happens to CO<sub>2</sub> over time?

Timeline	Mobile (%)	Residually trapped (%)	Dissolved (%)
End injection	36	36	28
1 yr	21	37	42
10 yr	18	35	47
20 yrs	18	34	48
100 yrs	12	26	62

*Example calculation from the CO2CRC Otway Stage 2C. These parameters are depending on characteristics of storage reservoir and are ONLY representative for the reservoir modelled.*

# Presentation Outline

- CO2CRC and its Otway Research Facility
- Past Major Project – Otway Stage 1
- Basis of Otway Stage 2
- Completed Appraisal Activity
- **Injection and Monitoring Activity**
- Anticipated Outcomes
- Future of the Otway Research Facility

# Stage 2C Injection Plan

Parameter	Description
Injectant	Buttress-1 gas
Injection Interval	1501 – 1512 mRT in CRC-2
Injection Mass	15,000 tonnes
Injection Rate	111 tonnes/day for 135 days
Injection Period	19 <sup>th</sup> November 2015 – 4 <sup>th</sup> May 2016





# Stage 2C Operation (2015 – 2020)

## GOAL


Safely complete seismic-focused, 2C injection experiment in a saline formation, such that it meets the scientific objectives and the results provide high quality research value to CCS knowledge.

## SCIENTIFIC OBJECTIVES

1. Detect injected Buttress gas in the subsurface; ascertain minimum detection limit;
2. Observe the gas plume development using time lapse seismic;
3. Verify stabilisation of the plume in the saline formation using time lapse seismic.



# Amplitude of time lapse signal with surface and buried geophone array



End injection

1 yr post injection

2 yr post injection

# Surface Monitoring




500 m

..... receiver lines  
..... backbone line

## Active & Passive seismic


- Buried seismic receiver array (908 single component geophones & 34 km fibre optic cable)
- Repeat (Vibroseis) & permanent seismic sources













# Downhole Monitoring

## CRC-2 Completions


- Injection interval and above zone isolations (SSDs)
- Gas injection and lift mandrels

### Monitoring tools

- Permanent pressure & temperature
- U-tube (tube in tube)
- Fibre Optic - DTS & acoustic

## CRC-1

- Seismic geophones (VSP)




# Monitoring plan

- Continual pressure and temperature monitoring
- Ongoing passive seismic monitoring
- During injection active seismic acquisition (permanent sources with surface 3D and receiver arrays)
- During and post injection - active seismic acquisition (vibroseis source with surface 3D and VSP receiver arrays)

Activity	2013	2014				2015				2016			2017		2018		2019		2020
	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	H2	H1	H2	H1	H2	H1	H2	H1
Approvals		◆ Spend auth.			◆ FID				◆ Inject auth.										
<i>Phase 4 - Execution</i>																			
CRC-2 Workover																			
Receiver Installation																			
Pit const. & seis source install.																			
CRC-2 Sgr Test																			
<i>Phase 5 - Operate Pt. 1</i>																			
VSP + 3D seismic baseline acq.																			
Injection (15kt @ 110t/day)																			
VSP + 3D seismic acq. (5kt)																			
VSP + 3D seismic acq. (10kt)																			
VSP + 3D seis. acq. (end inject.)																			
<i>Phase 6 - Operates Pt. 2</i>																			
3D seis. acq. (1 yr. post inject.)																			
3D seis. acq. (2 yr. post inject.)																			
Required Site Closure																			

- ◆ Key Milestones
- Planning / Ops Mgmt. Activity
- Activity relating to well operations
- Activity relating to seismic monitor



# Presentation Outline


- CO2CRC and its Otway Research Facility
- Past Major Project – Otway Stage 1
- Basis of Otway Stage 2
- Completed Appraisal Activity
- Injection and Monitoring Activity
- **Anticipated Outcomes**
- Future of the Otway Research Facility



## Stage 2 - Anticipated Outcomes

- ✓ Methodology for near well characterisation of CO<sub>2</sub> storage
- Demonstrated capability of time lapse seismic for imaging a CO<sub>2</sub> plume
  - Quantified comparison of seismic techniques for the monitoring of CO<sub>2</sub> plume migration
- Method for the prediction of plume stabilization
  - Verification of stabilisation using seismic and pressure monitoring in conjunction with plume modelling
  - Enhanced capability to utilise short term monitoring to calibrate long term model predictions

# Participants



## Supporting Partners



# Presentation Outline

- CO2CRC and its Otway Research Facility
- Past Major Project – Otway Stage 1
- Basis of Otway Stage 2
- Completed Appraisal Activity
- Injection and Monitoring Activity
- Anticipated Outcomes
- **Future of the Otway Research Facility**

# Future Otway Projects: Stage 3

## Stage 1: 2004 – 2009

### *Depleted Field Storage*

- ✓ Demonstrate safe transport, injection and storage of CO<sub>2</sub> in a structural trap

## Stage 2: 2009 – 2018


### *Saline Formation Storage*

- ✓ 2A :Drill CRC-2
- ✓ 2B: Measure parameters affecting residual and dissolution trapping in a saline formation
- 2C: Spatially track injected CO<sub>2</sub> in a saline formation

## Stage 3: 2014 – 2021+

### *Otway Subsurface Laboratory*

- Validate subsurface monitoring
- Trial storage management processes and technologies





# Otway Stage 3 - Project Overview

## 1 - Problem:

1. Potential cost, geographical, societal, or economic impediments to repeat, surface-based M&V.
2. Insufficient resolution or accuracy across regions of higher risk and uncertainty
3. Effectiveness of subsurface M&V alternatives, is poorly understood
4. Effectiveness of storage management is poorly understood

## 2 - Objective:

Appraisal, implementation, demonstration and validation of subsurface monitoring of a CO<sub>2</sub> storage system and storage operations at the CO2CRC Otway Facility.

## 3 - Goals:

1. Validation of subsurface M&V as alternation M&V option (cost, footprint, socio-political)
2. Expanded Otway facility to enable storage management field trials

# Utilising the capital at the Otway – A National Deep Earth Research Facility


CO2CRC's aims to develop innovative clean energy technologies, over the next 10 years, by further understanding and exploiting deep earth processes.

Through international collaborations we wish to establish a **National Deep Earth Research Facility** that will continue to undertake leading CCS research while pursuing opportunities in:

CCS Water Co-Production  
Management

Geothermal

Energy storage



# Modelled Seismic Detection

Key time steps	Relative gas volume detected					
	R1	R2	R3	R4	R5	R6*
end injection	74% (7,892 t)	82% (8,512 t)	84% (8,971 t)	76% (7,820 t)	83% (8,765 t)	70% (7,497 t)
1 year post injection	68% (5,763 t)	71% (6,071 t)	61% (5,408 t)	55% (4,670 t)	65% (5,577 t)	51% (4,567 t)
2 years post injection	67% (5,598 t)	69% (5,817 t)	59% (5,152 t)	53% (4,428 t)	64% (5,395 t)	49% (4,285 t)
*- unlikely case where cements are laterally extensive						